

TEST REPORT

No: 44506

Client Camden Boss Ltd
60 James Carter Road
Mildenhall
Suffolk
IP28 7DE

Client contact Mr J Hodson

Item/s tested Ceramic Terminal Block
Models : B10-3E (CHTB10/1N /2N /3N /4N)
Rating : 25A 450V, 5°C - 350°C

Sample/ tested / Conditions One sample / Good condition

Tested to EN 60598-1:2008+A11:2009 Section 14
(Screw Terminal tests only) and deemed to comply

Date sample received 27th December 2012

Test period 9th January 2013 – 15th January 2013

Date of Issue 28th January 2013

Tests carried out at 20 ± 5 ° C

Testing Officer  Gary A Read

Verified by  Peter Cross



0225

Form No: QF102-2
Issue No: 2
Issue Date: 21.07.11





Report No:	44506
Client:	Camden Boss Ltd


THIS REPORT APPLIES ONLY TO THE PARTICULAR SAMPLE UNIT(S) TESTED AND TO THE SPECIFIC TESTS CARRIED OUT AS DETAILED IN THIS REPORT.

SUMMARY

The sample unit submitted for testing has been checked in accordance with the following section of BS EN 60598-1:2008 + A11:2009 only:-

Section 14: Screw Terminal Tests

Photographic identification



Note : The terminal block is rated 25 Amps, but the sample tested was marked 57Amps.

Report Details

The above ceramic terminal block meets the requirements of section 14 of BS EN 60598-1:2008 + A11:2009

Result : Complies

Equipment used :944,640,641,376,378,377,

----- End of Report -----

